

Mineral Resources for Galaxy Gold Mine as at 29 June 2020

Orebody	SG	Mineral Resource Category											
		Measured			Indicated			M & I Sub-total			Inferred		
		Tonnes	Gold Grade	Gold Content	Tonnes	Gold Grade	Gold Content	Tonnes	Gold Grade	Gold Content	Tonnes	Gold Grade	Gold Content
		t/m3	t	g/t	oz	t	g/t	oz	t	g/t	oz	t	g/t
Galaxy Surface to Dyke**	2.73	-	-	-	-	-	-	-	-	-	291,000	3.19	29,845
Galaxy 17 Level Up	2.73	302,233	3.01	29,248	79,825	2.86	7,335	382,058	2.98	36,583	258,111	2.78	23,045
Galaxy Gap 17-24 Level	2.73	-	-	-	-	-	-	-	-	-	1,311,320	2.84	119,825
Galaxy 24 Level Down	2.73	1,867,951	2.67	160,413	750,215	2.37	57,245	2,618,166	2.59	217,657	522,609	2.61	43,908
Total Galaxy	2.73	2,170,183	2.72	189,661	830,040	2.42	64,580	3,000,224	2.64	254,241	2,383,040	2.83	216,623
Woodbine W & E Surface - 22 Level*	2.73	-	-	-	110,501	4.61	16,392	110,501	4.61	16,392	306,432	2.95	29,025
Woodbine 24 Level Down	2.73	344,856	3.57	39,580	277,372	3.04	27,099	622,228	3.33	66,679	768,832	3.34	82,660
Total Woodbine	2.73	344,856	3.57	39,580	387,873	3.49	43,491	732,729	3.53	83,070	1,075,264	3.23	111,686
Giles Surface - 23 Level*	2.73	-	-	-	263,558	4.15	35,149	263,558	4.15	35,149	271,260	3.65	31,820
Giles 23 Level Down	2.73	283,142	4.59	41,827	369,151	3.30	39,213	652,293	3.86	81,040	840,979	3.80	102,676
Total Giles	2.73	283,142	4.59	41,827	632,708	3.66	74,363	915,850	3.95	116,189	1,112,239	3.76	134,496
Princeton PS5	3.08	-	-	-	1,927,049	3.67	227,143	1,927,049	3.67	227,143	3,141,476	3.25	328,444
Princeton PS12	3.08	-	-	-	56,781	3.30	6,027	56,781	3.30	6,027	135,747	2.50	10,922
Princeton PS19	3.08	-	-	-	1,689,283	2.82	153,218	1,689,283	2.82	153,218	1,187,869	4.29	163,709
Total Princeton	3.08	-	-	-	3,673,113	3.27	386,388	3,673,113	3.27	386,388	4,465,092	3.50	503,074
Golden Hill	3.03	410,393	2.66	35,054	564,454	2.71	49,181	974,847	2.69	84,235	217,179	3.36	23,429
Agnes Top	2.80	-	-	-	561	2.07	37	561	2.07	37	870,632	1.75	49,016
Pioneer & Tiger-Trap	2.73	-	-	-	-	-	-	-	-	-	5,949,307	1.55	296,823
Ivy Shaft Pillar*	2.78	-	-	-	-	-	-	-	-	-	47,125	10.18	15,427
Ivy to Agnes 3-11 Level*	2.78	-	-	-	-	-	-	-	-	-	45,498	5.71	8,349
Ceska Shaft Pillar*	2.78	-	-	-	-	-	-	-	-	-	113,534	9.58	34,987
Woodbine South Dump	1.12	-	-	-	13,129	1.55	656	13,129	1.55	656	19,217	1.47	906
Woodbine West Dump	1.17	-	-	-	714	0.72	16	714	0.72	16	5,749	0.69	127
Woodbine W.West Dump	1.17	-	-	-	13,136	0.50	209	13,136	0.50	209	25,057	0.51	410
Hostel East Dump	1.41	-	-	-	958,401	0.76	23,562	958,401	0.76	23,562	164,506	0.68	3,581
Hostel West Dump	1.41	-	-	-	430,880	0.88	12,220	430,880	0.88	12,220	98,985	0.87	2,763
Biox North Dump	1.38	-	-	-	189,340	1.66	10,080	189,340	1.66	10,080	141,993	1.77	8,069
Grand Total		3,208,575	2.97	306,122	7,694,349	2.69	664,783	10,902,925	2.77	970,904	16,734,418	2.62	1,409,764

Notes:

- * Manual Mineral Resource estimate from block plans.
- ** Mineral Resources estimated from adjacent modelled areas for grade distribution; Orebody volume estimated from digital wireframe.
- Cut-off applied for Surface TSFs: 0.3 g/t.
- Cut-off applied for Underground Operations: 1.4 g/t.
- Cut-off applied for Open Pit (Agnes Top): 1.0 g/t.
- No geological losses have been applied.
- Commodity price utilised: USD1,600/oz.
- Mineral Resources are stated inclusive of Mineral Reserves.
- Mineral Resources are reported as total Mineral Resources and are not attributed.
- All orebodies are depleted for current mining.